Contractor: McCarty & Son, Inc. **Address:** 1161 Steinmentz Rd

Address: 0

City, State, ZIP: Ephrata, PA 17522

Change Order No: 7

Date: 2/21/2024

Project: Renos & Additions to Northern

Address: Lebanon Middle & High School

Architect's Project No: 3624

The contract is changed as follows:

Add \$ 57,040.98 Deduct **Contract Type:** Electrical **Notice to Proceed Date:** 12/8/2023

As a result of specific phasing requirements in the kitchen/existing gym area, the existing RTU and ductwork could not remain operational as it was in the way of the new renovations for the kitchen area. Now the new RTUs-01A & 01B are needed sooner than anticipated. However the new 480v power required to run the new RTUs is not available until later in the project. This COR provides the credit for the 480v services to RTU-01A and RTU-01B and deletes panel HK and associated panel feeder. The EC will provide temporary feeds via transformer fed from MDB2. Temporary feeds will be removed when permanent service becomes available from panel HD1A.

Additional Documentation Attached

 $\overline{\mathbf{A}}$

This Change Order is not valid until signed by the Owner, Architect, and Contractor.

Original Contract Amount	\$ 9,344,066.00
Net Change by previous Change Orders	\$ (33,695.38)
Contract Amount prior to this Change Order	\$ 9,310,370.62
Net Change by this Change Order	\$ 57,040.98
Contract Amount after this Change Order	\$ 9,367,411.60

Contract Time adjustment as a result of this Change Order
Date of Substantial Completion as of this Change Order

Days

Architect Crabtree Rohrbaugh & Assoc. 401 East Winding Hill Road Third Floor Mechanicsburg, PA 17055	Contractor McCarty & Son, Inc. 1161 Steinmentz Rd 0 Ephrata, PA 17522	Owner Northern Lebanon SD 345 School Drive 0 Fredricksburg, PA 17026
Ву:	Ву:	Ву:
Date:	Date:	Date:

Project Name: Northern Lebanon HS/MS

MEC Project No.:22007

COR Number: EC-012 Date: 02-16-2024

Moore Engineering Comments:

1. MEC takes no exception to the proposed COR. Please proceed with Option #2 (480V RTU solution).

of

Pages



MCCARTY & SON

"Quality and Pride in Workmanship"

₩\\\

ELECTRICAL CONTRACTORS

Commercial & Industrial

1161 Steinmetz Road Ephrata, PA 17522 (717) 626-9580 (717) 721-7680 Email: bmccarty@dejazzd.com

No. 8661R2

PROPOSAL SUBMITTED TO	PHONE	DATE
Northern Lebanon School District		February 14, 2024
STREET	PROJECT NAME	
345 School Drive	RTU 01A and 01B	
CITY, STATE and ZIP CODE	PROJECT LOCATION	
Fredericksburg, PA 17026		MS and HS Project
ARCHITECT	ATTENTION	
	Attn: Bradly Reist	
We hereby submit specifications and estimates for:		
Revised price quotation options for the R	ΓU 01A and RTU 01B. Please see at	tached.
	Price Quotation:	See attached
	Price Quotation:	See attached
	Price Quotation:	See attached
Thank you for giving us the opportunity to s		
Thank you for giving us the opportunity to s		
Thank you for giving us the opportunity to s We Propose hereby to furnish material and laborates.	supply you with a quote for this work	bove specifications, for the sum of:
	supply you with a quote for this work	i.

All material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tornado and other necessary insurance. Our workers are fully covered by Workman's Compensation Insurance.

Acceptance of Proposal – The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Date of Acceptance:

Authorized Signature

Note: This proposal may be withdrawn by us if not accepted within

days

nature _____



MCCARTY & SON

Electrical Contractors Commercial & Industrial

1161 Steinmetz Road Ephrata, PA 17522 (717) 626-9580 (717) 721-7680 bmccarty@dejazzd.com

"Quality and Pride in Workmanship"

February 14, 2024

Northern Lebanon School District 345 School Drive Fredericksburg, PA 17026

RE: Northern Lebanon Middle School / High School Project Proposal 8661R2 breakdown

To Whom It May Concern,

Below are revised option breakdowns for the RTU-01A and RTU-01B:

Option #1:

Credit 480V services to RTU-01A and RTU-01B and delete panel HK and associated panel feeder. Provide 208V services for RTU-01A and RTU-01B via switchboard MDB2:

New Construction

- Renovations
- · Fire Alarm System Installation
- · Security System Installation
- · Sound System Installation
- Data Networking
- Fiber Optics
- Power Distribution
- · Control Wiring
- · Phone and Cable Wiring
- · Outdoor Lighting
- · Distribution 13KV
- · Bucket Truck Service
- · Design Build
- · Plant Maintenance

Material Credit:

290'	3" EMT Conduit
4	3" EMT Connector
36	3" EMT Coupling
4	3" Bushing
1,200'	300 KCMILL THHN Copper wire
300'	#3 THHN Copper Wire
Lot	Hangers and Supports
1	24x24x8 Pull Box
Lot	Colonial Panel HK Credit
2	Square D 100A NEMA 3R Disconnect
160'	1 ¼" EMT Conduit
4	1 1/4" EMT Connector
18	1 1/4" EMT Coupling
4	1 1/4" EMT Bushing
10'	1 1/4" Flex
2	1 1/4" Flex Connector
2	1 1/4" Flex Connector 90 Degree
540'	#4 THHN Copper Wire
180'	#8 THHN Copper Wire
Lot	Hangers and Supports
2 Roc	of Penetrations



MCCARTY & SON

-_

Electrical Contractors Commercial & Industrial

1161 Steinmetz Road Ephrata, PA 17522 (717) 626-9580 (717) 721-7680 bmccarty@dejazzd.com

"Quality and Pride in Workmanship"

Material Add:

2	Cutler Hammer ED3150 Circuit Breaker	53
-		

1 Cutler Hammer KPRL4ED Kit

1 Cutler Hammer 6554C01H05 (3x)

970' 3" EMT Conduit 14 3" EMT Connectors 120 3" EMT Coupling 20 3" Bushing 20' 3" Sealtight

2 3" Sealtight Connector

2 3" Sealtight Connector 90 Degree

2 3" Ridgid Coupling

1,665' 400 KCM THHN Copper Wire 1,455' 350 KCM THHN Copper Wire 1,040' 1/0 THHN Copper Wire

Lot Hangers and Supports

Roof Penetrations

2 Roof Penetrations
4 24x24x12 Pull Box
12 2 Cond Insulated Lug

4 2 Cond insulated Lug Lot Pulling Equipment 12 Reducing Pins

Sound System Installation

· Security System Installation

. Fire Alarm System Installation

Data Networking

New Construction

· Renovations

AND THE STREET

· Fiber Optics

· Power Distribution

Control Wiring

· Phone and Cable Wiring

· Outdoor Lighting

· Distribution 13KV

· Bucket Truck Service

Design - Build

Plant Maintenance

Material Credit: (15,984.99)
Material Add: 47,088.98
Net Material Add: 31,103.99

Net Material Add: 3 Labor Credit: (105 hrs.) Labor Add: 444 hrs.

Net Labor Add: 339 hrs.

 Material:
 31,103.99

 Overhead & Profit:
 4,665.60

 Labor (339 hrs.):
 31,649.04

 Bid Bond:
 1,739.40

Price Quotation Option #1: 69,158.03



MCCARTY & SON

√₩\/_

Electrical Contractors Commercial & Industrial

1161 Steinmetz Road

(717) 626-9580 (717) 721-7680

"Quality and Pride if Assistantiv" to RTU-01A and RTU-01B and delete panel HK and associated panel feeder. Provide temporary 480V feeds via transformer fed from MDB2. Temporary feeds will be removed when permanent services become available from panel HD1A:

Material Credit:

290' 3" EMT Conduit 4 3" EMT Connector 36 3" EMT Coupling

4 3" Bushing

1,200' 300 KCMILL THHN Copper wire

300' #3 THHN Copper Wire Lot Hangers and Supports

1 24x24x8 Pull Box

Lot Colonial Panel HK Credit

5 Square D 100A NEMA 3R Disconnect

160' 1 1/4" EMT Conduit
4 1 1/4" EMT Connector
18 1 1/4" EMT Coupling
4 1 1/4" EMT Bushing

10' 1 1/4" Flex

2 1 1/4" Flex Connector

2 1 1/4" Flex Connector 90 Degree

540' #4 THHN Copper Wire 180' #8 THHN Copper Wire Lot Hangers and Supports 2 Roof Penetrations

Power Distribution

· Data Networking

· Fiber Optics

New Construction

· Fire Alarm System Installation

· Security System Installation

. Sound System Installation

Renovations

· Control Wiring

· Phone and Cable Wiring

· Outdoor Lighting

Distribution 13KV

Bucket Truck Service

· Design - Build

Plant Maintenance

Material Add:

1 Cutler Hammer CLD3600 Circuit Breaker

Cutler Hammer KPRL4LD Kit
Cutler Hammer 6554C01H03

2 Square D 100A NEMA 1 Disconnect

6 70 Amp Fuses

1 Square D Transformer XR150KEX

Square D Lug Kit KAU-KIT Lot Unload and Set in place Square D Ground Kit

3 70 Amp Circuit Breaker (exchanged 15 amp circuit breaker in

panel HD1A)

40' 3" Flex Conduit 2 3" Flex Connector

3 3" Flex Connector 90 Degree

6 3" Bushing

540' 250 KCM Aluminum Wire

180' 2/0 Aluminum Wire

Lot Grounding for Transformer

Lot Hangers and supports for Transformer



· New Construction

· Fire Alarm System Installation

· Security System Installation

· Sound System Installation

· Data Networking

· Power Distribution

· Phone and Cable Wiring

· Control Wiring

· Outdoor Lighting

· Distribution 13KV

· Bucket Truck Service

· Design - Build

· Fiber Optics

· Renovations

MCCARTY & SON

Electrical Contractors Commercial & Industrial

1161 Steinmetz Road Ephrata, PA 17522 (717) 626-9580 (717) 721-7680 bmccarty@dejazzd.com

"Quality and Pride in Workmanship"

650'	Aluminum MC 3-#1 and 1-#4
3	MC Cable Connector
Lot	Hangers and Supports
8	2 Conductor Insulated Lug
3	K.O. Seals 3"
2	K.O. Seals 2"
1	16x16x6 Pull Box
480'	1 1/4" EMT Conduit
8	11/4" EMT Connector
60	11/4" EMT Coupling
8	11/4" Bushing
20'	11/4" Greenfield
2	11/4" Flex Connector
2	11/4" Flex Connector 90 Degree
1,620'	#4 THHN Copper Wire
540'	#6 THHN Copper Wire
Lot	Hangers and Supports

Material Credit:	(15,984.99)
Material Add:	36,411.50
Net Material Add:	20,426.51
1 - 1 1:1.	/105 bys 1

Roof Penetrations

Labor Credit: (105 hrs.) Labor Add: 449 hrs.

Net Labor Add: 344 hrs.

Material:	20,426.51
Overhead & Profit:	3,063.98
Labor (344 hrs.):	32,115.84
Bid Bond:	1,434.65

Price Quotation Option #2: 57,040.98

If you have any questions, please feel free to give our office a call.

Sincerely,

Plant Maintenance

Kyle H. McCarty